## Scroby Sands 2008





The first of these was the export cable replacement project undertaken at Scroby Sands OWF. The project called for the highest specification in diving equipment and experienced personnel. Throughout the operation the divers worked around the clock to achieve the recovery, replacement and reburial of one of the three export cables.

The project was undertaken during the summer of 2008 with divers working in variable conditions, deburial of the cable was the first task, followed by careful recovery of the now redundant cable. Once the new cable was laid OPU's vertical injector was utilised in order to bury the majority of the cable with divers burying the last of the cable up to the I-tube and successfully completing the tie-in and shore-ends works.



## Services

- Export cable deburial, replacement and reburial Shore-end installation
- I-tube bolt torque operations
  Articulated piping installation

## Osiris Marine Services UK HQ

Unit 2a Sabella House, The Crossing Business Park, Riparian Way, Cross Hills, Nr Skipton, North Yorkshire BD20 7BW T: +44 (0)1535 631141 E: info@osirismarineservices.com W: www.osirismarineservices.com

## Osiris Marine Services Denmark

T: +45 2917 4101 E: info@osirismarineservices.dk W: www.osirismarineservices.dk



















